

## **SAP 059-607-022 etc. (2018 Overlays)**

### COMMONLY OVERLOOKED ITEMS and/or SPECIAL ITEMS OF INTEREST

(This sheet is not part of the proposal)

*Below is a list of commonly overlooked items and items of special interest. The purpose of this list is to bring attention to some of these items. This shall not be considered an all inclusive list. The contractor shall review the entire set of plans and Special Provisions.*

- **The Schedule of Bid Prices must be obtained from the Pipestone County Highway Department by submitting your company name, address, phone no., fax no., and email address via email to [highway@co.pipestone.mn.us](mailto:highway@co.pipestone.mn.us) or by calling 507-825-1245.** Obtaining the Schedule of Bid Prices places you on the plan holders list. You will also receive any addendums that may be issued for this project.
- Return the **ENTIRE** proposal with your bid. (See specification 1206)
- See specification 1505 in reference to work by others in Pipestone.
- The Contractor shall apply calcium chloride for dust control at all farm sites and intersections.
- Railroad Protective Liability Insurance is required on this contract. Early contact and coordination with the Railroad is strongly encouraged. (Cost shall be included in the unit price bid).
- The Contractor shall coordinate operations and minimize impacts to community events, business operations, and other social functions.
- All trucks used to haul material onto a project shall have a tare weight from a certified scale. (See specification 1901)
- Certification of the bituminous plant will be at the contractor's expense.
- All incentives/disincentives will be reduced by 50% of the rate specified in (2399) PAVEMENT SURFACE SMOOTHNESS.
- The Contractor shall secure the services of a private firm to run the Smoothness test.
- On project **SAP 059-610-039** the Contractor shall notch out the existing shouldering material to accommodate pavement widening to a width of 1' and a depth of 3" and then place 3" of Type SP 9.5 Wearing Course Mixture (See plan sheet 3 of 4).
- On project **SAP 059-610-038** the Contractor shall place approximately 66 tons of Type SP 9.5 Wearing Course Mixture (2,B) for leveling patches in 3 different locations. This quantity shall be paver laid prior to mainline paving.
- A. On project **SAP 059-623-004** Pipestone County will furnish 2 adjusting rings at no cost to the Contractor for adjusting 2 valve boxes (other adjusting rings shall be included in the unit price bid). Any other adjusting of valve boxes will be paid for as one unit under Item No. 2504.602 (Adjust Valve Box – Water)
- Pipestone has adopted an aggregate production tax.
- Fill out Certification of Aggregates and Granular Materials form (G&B-104).
- Fill out the Non-Collusion Affidavit.
- Fill out Responsible Contractor Verification and Certification of Compliance forms.
- Acknowledge all addenda. (If any)